

## **CHAPTER 33**

### **SAFEGUARDS DURING CONSTRUCTION**

[No change to Sections 3301 to 3312. Add Section 3313 at the end].

#### **SECTION 3313 DESIGN LOADS ON STRUCTURES DURING CONSTRUCTION**

**3301.1 Design loads.** The design loads on partially completed structures and temporary structures, including scaffolding, bracing, and shoring, shall be in accordance with ASCE 37.

**3301.2 Structural integrity during construction.** The structural integrity of partially completed and temporary structures shall comply with Section 1.3.2 of ASCE 37.